METRO

THEATRE SYDNEY

THE METRO THEATRE TECHNICAL SPECIFICATIONS

Current as of October 2026

Metro Theatre 3D Walkthrough

https://www.3dinsights.com.au/viewer/century/metro/

CONTACTS

The Metro Theatre
624 George Street
Sydney Australia, 2000
+61 2 9660 9060 (Box Office)

Century Venues

105 Victoria Road
Marrickville NSW Australia, 2205

+61 2 9519 9231

INDICATIVE CHARGES – METRO THEATRE

The items listed below may incur additional charges and should be considered during event planning and budgeting. Applicable charges will be itemised and included in the final venue settlement following the event.

Early / Late Access

Additional venue hire and staffing charges may apply for access required outside the contracted hire period.

House Audio Component

The House Audio Component, as detailed within this document, is included as part of the standard venue hire.

House Lighting Component

The House Lighting Component, as detailed within this document, is included as part of the standard venue hire.

Additional Production Items

Please contact the Event Manager or Production Manager regarding availability and associated charges for production equipment or services not included within the standard venue specification.

Technical Advancing & Additional Resources

All technical advancing, production requirements, and any additional equipment or staffing requirements should be coordinated through your Event Coordinator. Associated charges may apply, subject to event requirements.

STAGE DIMENSIONS

Stage Width	10.1m
Stage Height from Floor	970mm
Stage to ceiling height	4.6m
DSE to rear wall	6m
Stage Rake	0deg rake. Flat Floor
Stage Surface	Timber floor, carpeted

AUDITORIUM DIMENSIONS

DSE to Audio & Lighting Mix Pos	12.8m
DSE to rear of room	24m
Theatre Floor Width	19.4m

POWER

Lighting

4 x 32amp 3 Phase outlets located Stage Right. 2 are in use for house lighting rig.

Audio

2 x 32amp 3 Phase outlets located on Stage Left.
1 x 32amp 3 Phase outlet located on Stage Right.

STAGE FITTINGS

2 x Black velour Legs Upstage Black Smother

HOUSE TRUSS

FOH Truss
1x tri truss located over dancefloor on 2x 500kg chain blocks 3.5m from DSE

Upstage Truss
1x tri-truss, 9.0m width on 2/3x 500kg chain blocks 6m from DSE.

LIGHTING

Please see LX plot on following page.

Dimmers	12ch, 1x Jands FP12
Control	Grand MA3 Compact XT
Data Splitter	Jands DD6-2

10 of ACME XA400 Energy Spot Pro
24 of ACME Stage Par 100 Colour
8 of Acme Ginamp
6 of Acme Stage Blinder
4 of ACME RGBW Stage Par Colour
5 of ETC Source4 Profile
2 of 1K Selecon Wash Lights

Additional Lighting Packages Available
Please contact your Event Manager / Production Manager for prices and availability

Acme Ozone
Atomic Strobes
Duet/4 Way Blinder
Hazer
1.2K Explorer Followspot
Dry Ice Machine
Upright Truss & Baseplates

Followspot Operators

FOH followspot operators are booked by Event /Production Manager on a minimum 4 hour call.

RIGGING

All rigging and fly system requirements installed and operated by inhouse riggers only. The Production Manager must approve all additional rigging requirements in advance.

AUDIO VISUAL

The Metro Theatre has a 5.5m x 2.5m LED Screen hung from the US Truss. The screen comes with a HDMI input at SR or FOH.

Resolution: 840px H x 1848px W

FOH Mix to Rear Truss	18.8m
Room Truss to Rear Truss	9.5m

AUDIO

FOH Speaker System

L'Acoustics V-Dosc Full Range	8
L'Acoustics SB218	8
Nexo Alpha M3 Down Fill & In Fill	4
Nexo Alpha B1 In Fill	2

Crown Amps & Dolby Lake Processing

FOH Control

Allen & Heath Dlive S5000 with 64/32 IO
Waves and Dante Cards

Monitor Control

Allen & Heath Dlive S3000 with 64/32 IO

Monitor System

Wayloud Monitors	9
EVX	2
18" Subs	3 (2x sidefill, 1x drum fill)

6 of Monitor Mixes plus Drum, Cue Mix
2 of Side fill mixes

System Info

Multicore	60 channel with 2 way split

In House Audio Equipment

Shure Beta 52	1
Shure Beta 91	1
Sennheiser 904	5
Shure SM81	5
Rode NT5	2
Beyer Dynamic M88	1
Sennheiser 906	2
Shure Beta 58	4
Shure Sm58	6
Shure Sm57	9
Shure Beta 56	2
Radial PC DI	2
Radial Mono Active DI	4
Radial Stereo Active DI	4
Radial Mono Passive DI	1
Radial Stereo Passive DI	1

Short Stands	15
Tall Stands	14

Available For Hire
Up to 4 x Shure ULXD Handheld W/ B58A Capsule
Up to 8 Sennheiser G4 IEM Transmitter and Beltpack - Stereo

DRESSING ROOMS & PRODUCTION OFFICES

1 x Dressing Room downstairs, Stage Right
1 x Dressing Room upstairs, Stage Right
1 x Production Office downstairs, Stage Right

All rooms equipped with wall mirrors and mirror lighting.
Toilets and showers available in both dressing rooms.
Tea and coffee facilities available.

Internet Access

Wireless Network Name	Airport Extreme
Wireless Network Password	METRO.624

LOADING AREAS

Loading Dock located via Central Lane.

Loading Door Height	2000mm
Loading Door Width	1480mm
Distance from dock to stage	7m from door to stairs
	29 Stairs up to landing
Loading Dock	3.6m Clearance / 5.5m wide x 10m deep

METRO THEATRE HOUSE RULES

All doors, stage or house must be clear at all times for access.
All stage equipment must enter via Loading Dock.
Only house riggers may operate rigging equipment or rig.
Do not adjust stage drapery.
Load out to be carried out safely and immediately after conclusion of performance.